# **Dalmia**BHARAT CEMENT

# DALMIA CEMENT (B) LIMITED - ARIYALUR



## **MECHANICAL**

Issue No. 01 Rev. No: 00 Effective Date: 28.02.2018 SOP/MEC/147

Issued By: M.R Approved By: HOD-Mechanical

# SOP FOR OR HYDRA OPERATION

#### **SOP FOR OR HYDRA OPERATION**

**Scope** : This SOP is applicable to Safe working of Mobile crane Operation

**Responsibility** : Operator

**Accountability** : Section Engineer.

#### PPE:

1. Safety helmet

- 2. Safety shoe
- 3. Safety shoe
- 4. Safety Belt
- 5. Nose Mask.
- 6.Asbestos Gloves.

#### **Training needs:**

- 1. Emergency preparedness
- 2. Fire Fighting
- 3. Hydraulic operation

#### **Procedure:**

- 1) Complete the check list and start the Vehicle.
- 2) Remove all chock blocks Under the wheels
- 3) Check for loose objects on Runways or road.
- 4) Hydra operators shall not engage in any other practice that will divert their attention while operating the equipment.
- 5) Operator must make a complete walk around the equipment to ensure that people are clear of the equipment, all nearby are equipment is in a safe distance
- 6) Check for overhead electrical hazards, safe site conditions, weather and excessive wind.
- 7) Check and Verify that ground conditions at work locations are stable and provide adequate support.

# **Dalmia**

# DALMIA CEMENT (B) LIMITED - ARIYALUR



## **MECHANICAL**

Issue No. 01	<b>Rev. No: 00</b>	Effective Date: 28.02.2018   SOP/MEC/147				
Issued By: M.R		Approved By: HOD-Mechanical				
SOP FOR OR HYDRA OPERATION						

- 8) Put Barricades, warning signs or other methods must be used to prevent entry into a lift area or turn radius of the hydra.
- 9) All controls must be tested by the operator prior to operating the equipment.
- 10) All loads must be rigged by a Qualified Rigger.
- 11) Don't use tools and tackles without color codification.
- 12) Know the weight of the components before attempt a Lifting. Don't lift unknown Weight or equipment's.
- 13) Don't push or pull the lifting objects by using hydra boom or hook .
- 14) Don't bypass the Safety device installed on the hydra.
- 15) After completion of work remove all Barricades & warning signs from that area.
- 16) Park the hydra always at safe place with wheel chock.
- 17) Ensure Crane unloaded condition before the Rigger attempt to Remove Slings from Crane

## **Emergency / Emergency Shut OFF:**

1. If any injury takes place, provide First aid and inform to the Safety department or Call Emergency number 3108/9865152222

# Records/Annexure:

1. JSA as enclosed below

# **Job Safety Analysis:**

Job Safety Analysis	Job: HYDRA OPERATION	Date:28.2.2018	Analysis by: Section Engineer	Reviewed by: Head	Section
Title of employee doing job: Technician	Supervisor: Section Engineer	Department: Mechanical	Section: Cement Plant	Approved by: Mechanical	HOD
job: Technician Engineer Mechanical Plant Mechanical  Required/recommended PPF: Safety belief Safety shoe & Safety belt goggles					

Sequence of Basic Job	Potential Hazards	Recommended Safe	What Could Go	Corrective Action



# DALMIA CEMENT (B) LIMITED - ARIYALUR



# **MECHANICAL**

Issue No. 01 Rev. No: 00 Effective Date: 28.02.2018 SOP/MEC/147

Issued By: M.R Approved By: HOD-Mechanical

# SOP FOR OR HYDRA OPERATION

Steps		Job Procedure	Wrong	
Moving the hydra	Slip / Fall /caught in between	Use proper lifting tools	Failure of lifting tools	Use tested tools Deploy trained manpower.
Operating the hydra	Slip / Fall /caught in between	Use proper lifting tools	Failure of hydraulic components	Use tested tools  Deploy trained manpower.
Lifting load	Slip / Fall	Use proper lifting tool	Failure of lifting tools	Use tested tools  Deploy trained  manpower.