# **Dalmia**BHARAT CEMENT

## **DALMIA CEMENT (B) LIMITED – Ariyalur**



#### MECHANICAL SOP

Issue No. 01	Rev. No: 02	Effe	ctive Date: 17/10/2017	SOP/MEC/042				
Issued By: M.R			Approved By: HOD-Mechanical.					
RABH DP High								

Scope: Maintenance in RABH while DP is high

Responsibility: General Fitter/ Millwright Fitter / Supervisor Accountability: Mechanical-Section Engineer / Section Head

PPE:

1. Safety helmet.

- 2. Safety shoe.
- 3. Nose Mask.
- 4. Hand Gloves.

#### **TOOLS:**

1. Box spanner set.

2. Ring spanner set.

### **Hazard Analysis:**

Risks associated: Mitigating Measures

Material or Gases entry : Ensure all material incoming Drives & Ducts Isolated.

Oxygen deficiency : Confined space permit is essential to enter in to the RABH.

Heat : Confined space permit is essential to enter in to the RABH

#### **Procedure:**

- 1. Check the compressor air pressure(5-7 kg/sq.cm) for poppet valve operation
- 2. Check the leakages in doors and joints if so arrest the same with proper sealants
- 3. check the cylinder guide plate for free movement of cylinder
- 4. Check the operating of all cylinders
- 5. Check the Sequence of all poppet valve cylinders
- 6. Check for Bags Coating
- 7. Check for Solenoid valve condition/operation
- 8. Check for Poppet damper closing percentage(can be done only in shut down)



## **DALMIA CEMENT (B) LIMITED – Ariyalur**



#### **MECHANICAL SOP**

Issue No. 01	Rev. No: 02	Effe	ctive Date: 17/10/2017	SOP/MEC/042			
Issued By: M.R			Approved By: HOD-Mechanical.				
RABH DP High							

- 9. Check for Ducts plugged with dust
- 10. RA fan damper closed physically due to slip of joints
- 11. Check for outlet Dampers may have closed

## **Emergency / Emergency Shut OFF:**

1. If any injury takes place, provide First aid and inform to the Safety department or Call Emergency number 3108/9865152222

## **Records/Annexure:**

- 1. Refer Line clearance certificates.
- 2. JSA as enclosed below

Job Safety	Job: RABH DP High Date: 01/09/2014		Analysis by: Section	Analysis by: Section		
Analysis			Engineer	Engineer		
Title of employee doing job:	Supervisor: Section Engineer	Department: Mechanical	Section: RVRM	Approved by: HOD-Mechanical.		

### Req'd/recommended PPE:

Sequence of Basic Job Steps	Potential Hazards	Recommended Safe Job Procedure	What Could Go Wrong	Corrective Action		
Cool The RABH chamber for inspection	For cooling the mill Doors to be kept in open condition.	Barricade the inspection doors Way	Heavy suction from the doors may suck you or your belonging	Keep yourself away from the Inspection doors during Cooling - Fan running condition		
RABH Internals Inspection	Burning injury	Always use hand Glove(must) during internals inspection	Other parts of the Body may touch with Hot surfaces of the mill	Competent person only allowed for Mill inspection.		



# DALMIA CEMENT (B) LIMITED –Ariyalur



## **MECHANICAL SOP**

Issue No. 01	Rev. No: 02	Effe	ctive Date: 17/10/2017	SOP/MEC/042			
Issued By: M.R			Approved By: HOD-Mechanical.				
RABH DP High							

## **Isolation Matrix:**

## solation Matrix:

S. N o	Activity	Tag / Name of the Equipment					
		Isolation Type					
		Electrical Energy	Other Energy				

1	RAW MILL BAG HOUSE INSPECTION	NAME AND TAG FOR THE	421FN1 RAW MILL BAG HOUSE FAN	361LD3 BY-PASS DUCT DAMPER IN CLOSED CONDITION	361FN3 RAW MILL FAN	POPPET DAMPERS COMPRESSOR COMMON AIR LINE VALVE TO BE CLOSED
	( OFF LINE	EQUIPMENT				
	INSPECTION)		421FN2 REVERESE AIR FAN	BAG HOUSE BOTTOM ROTARY AIR LOCK		